

高崎393180

地番	1 ①			
NO	Xn	Yn	Yn+1-Yn-1	Xn · (Yn+1-Yn-1)
P-30	34041.533	-68840.684	-18.627	-634091.635191
P30	34044.329	-68856.939	-14.049	-478288.778121
P29	34055.160	-68854.733	3.176	108159.188160
P-33	34059.489	-68853.763	15.308	521382.657612
P-32	34056.982	-68839.425	15.451	526214.428882
P-31	34055.319	-68838.312	-1.259	-42875.646621
合計				500.214721
合計面積				250.1073605
地積				250.10
				㎡

地番	2 ②			
NO	Xn	Yn	Yn+1-Yn-1	Xn · (Yn+1-Yn-1)
2543	34055.798	-68834.161	-7.299	-248573.269602
P-32	34056.982	-68839.425	-19.602	-667584.961164
P-33	34059.489	-68853.763	-14.185	-483133.851465
P28	34060.172	-68853.610	0.427	14543.693444
P27	34061.300	-68853.336	3.230	110017.999000
P-29	34072.206	-68850.380	20.051	683181.802506
P-28	34069.265	-68833.285	18.254	621900.363310
P-27	34067.625	-68832.126	-0.876	-29843.239500
合計				508.536529
合計面積				254.2682645
地積				254.26
				㎡

地番	3 ②-2			
NO	Xn	Yn	Yn+1-Yn-1	Xn · (Yn+1-Yn-1)
P-26	34040.847	-68836.733	-3.080	-104845.808760
5002	34040.934	-68837.241	-2.483	-84523.639122
2544	34041.280	-68839.216	-3.443	-117204.127040
P-30	34041.533	-68840.684	0.904	30773.545832
P-31	34055.319	-68838.312	1.259	42875.646621
P-32	34056.982	-68839.425	4.151	141370.532282
2543	34055.798	-68834.161	2.692	91678.208216
合計				124.358029
合計面積				62.1790145
地積				62.17
				㎡

地番	4 ③			
NO	Xn	Yn	Yn+1-Yn-1	Xn · (Yn+1-Yn-1)
P-20	34076.908	-68830.529	1.340	45663.056720
P-27	34067.625	-68832.126	-2.756	-93890.374500
P-28	34069.265	-68833.285	-18.254	-621900.363310
P-29	34072.206	-68850.380	-13.432	-457657.870992
P26	34085.719	-68846.717	3.917	133513.761323
				-68846.463
				-68835.078
				-68833.919
				-68834.624
				-68833.466
合計				482.157052
合計面積				241.0785260
地積				241.07
				㎡

※支線・支柱について
地支線は根開き 5 m
支柱は根開き 3.5 m
で検討しております

建柱作業のある位置については1m×1mの掘削を行います。
建柱位置付近には水道やガス管など埋設を行わないよう、お願いします。
また、建柱時ブロック塀基礎崩しを実施することがあります。

